



Narrative of survey

The purpose of this survey was to subdivide the Southeast 1/4 of Section 33, Township 4 North, Range 29 East W. M. so that it could be determined if County Road # 1184, Bartley Road, was within the dedicated Right-of-Way.

The Center 1/4 Corner was located by intersecting lines between opposite 1/4 corners, which were traversed through. The 1/16 corners were all located by single proportion on the exteriors of the quarter sections. The Southeast 1/16th corner was located by intersecting the lines between the opposite 1/16th corners. The 1/16th corners along portions of North Ash Road #1181, East Harding Avenue # 1182, South Ash Road # 1183, North Loop Road # 1175, and Stage Gulch Road # 1186 were set to increase the frequency of monumentation along these Road

Bearing Base used was N 89° 17' 16" E from the South 1/4 Corner of Section 33 to the Southeast Corner of Section 33 from Edward's 1994 Area 1 Umatilla County Monumentation Survey, C. S. # 95-60-B. Instrument Used was a Wild T-16 one-minute theodolite with a Wild DI-5 E.D.M.

- LEGEND
- ✚ FOUND SECTION CORNER AS NOTED
 - ✚ FOUND 1/4 OR 1/16TH CORNER AS NOTED
 - SET 5/8" X 30" IRON PIN WITH PLASTIC CAP MARKED "UMA. CO. RD. DEPT. ... LS 2627"
 - △ SET RR SPIKE WITH PUNCH MARK STAMPED 2627
 - () DENOTES RECORD BEARINGS AND DISTANCES FROM C.S. # 95-60-B BY EDWARDS

5-96
 KK
 96-70-C

REGISTERED PROFESSIONAL LAND SURVEYOR
 Gary R. Roberts
 OREGON
 JULY 25, 1988
 GARY R. ROBERTS
 2627
 RENEWS 12-31-98

UMATILLA COUNTY ROAD DEPT 3920 Westgate Pendleton, Oregon 97801		
Survey for: County Road Right of Way Monumentation		
Located: Section 33, Township 4 North, Range 29 East of the Willamette Meridian		
Survey By: Gary Roberts	Drawn By: Jeanne Gorham	Checked By: Gary Roberts
Scale: 1" = 300'	Date: May 1996	Sheet: 1 of 1