



- LEGEND**
- SET A 5/8" x 24" IRON REBAR W/ A 1 1/8" ORANGE PLASTIC CAP STAMPED WTS AND 56295LS
 - ⊙ FOUND GLO BRASS CAP BY OTIS GOULD
 - FOUND BRASS CAP BY EDWARDS, SURVEYS 90-52-A AND 90-53-A
 - COMPUTED POINT
- R1 GLO CONTRACT #83 DATED JULY 22, 1859 BY DAVID P. THOMPSON
- R2 GLO CONTRACT #93 DATED SEPTEMBER 11, 1860 BY EBENEZER HAFT
- R3 GROUP No. 217 DATED JANUARY 26, 1938 BY OTIS O. GOULD
- R4 COUNTY SURVEY 82-115-A
- R5 COUNTY SURVEY 90-52-A
- R6 COUNTY SURVEY 90-53-A
- R7 COUNTY SURVEY 91-34-C
- R8 COUNTY SURVEY 09-68-C

BASIS OF BEARINGS
 Bearings are based on GPS derived grid bearings rotated 0°47'33" clockwise to obtain the bearings shown on this map. Distances shown are true ground distances.

TABLE OF ADJUSTED AREAS

AREA ID	ACRES	HOW ADJUSTED	ATTACHED TO
AREA "A"	15.10	TAX LOT 6200	TAX LOT 5400
AREA "B"	7.52	TAX LOT 5900	TAX LOT 6200
AREA "C"	38.22	TAX LOT 6200	TAX LOT 5900
AREA "D"	52.33	TAX LOT 5400	TAX LOT 6200

NARRATIVE OF SURVEY

This survey was performed at the request of Mr. Kent Madison. The purpose of the survey was to monument the proposed new boundary as shown hereon between Tax Lots 5400, 5900, and 6200. The data from this survey will be used to prepare the legal descriptions for the necessary conveyances and the resultant boundaries of these three Tax lots.

This boundary adjustment is the third in a series of three boundary adjustments being performed on Tax Lot 5900. The surveys of each of the prior adjustments are being recorded separately and should be consulted along with this survey for a history of the GLO corner establishments as well as a total record of the changes to Tax Lot 5900 and the surrounding tax lots which were also involved.

The final acreages for each of the Tax Lots shown are based on the initial acreage shown on the Assessor's maps plus or minus the measured acreage in the areas being moved into or out of each tax lot except for Tax Lot 6200. The final acreage shown for Tax Lot 6200 is the actual measured acreage. To arrive at the final acreage of Tax Lot 6200, an additional 6.96 acres were added to the original 160 acres to account for the area inside of the County Road. This is to insure that Tax Lot 6200 has a total of 160 unencumbered acres. This survey was performed with a Trimble R7/ R8 RTK GPS system operated in Real Time mode.

TAX LOT 5400
 AREA BEFORE ADJUSTMENT = 1320.98 ACRES
 AREA AFTER ADJUSTMENT = 1283.75 ACRES

LINE TABLE 1

LINE No.	BEARING	DISTANCE
L1	N04°22'18"W	579.33'
L2	N01°56'17"W	410.88'
L3	N01°48'00"W	280.00'
L4	N17°09'21"E	486.57'
L5	N03°52'51"E	140.27'
L6	N16°15'19"E	298.74'
L7	N15°16'23"E	181.60'
L8	N21°00'14"E	240.01'
L9	N13°35'09"E	141.71'
L10	N15°44'02"E	625.97'
L11	N19°46'45"E	952.39'
L12	N37°08'27"E	540.07'
L13	N39°18'15"E	226.61'
L14	N89°59'51"W	678.18'
L15	S89°59'51"E	1318.13'
L16	S89°34'41"E	474.80'
L17	S89°34'41"W	474.80'
L18	S89°59'51"E	702.84'
L19	N89°59'51"W	615.86'
L20	N19°46'45"E	332.75'
L21	N19°46'45"E	619.64'
L22	S00°03'15"W	1188.99'
L23	N00°03'15"E	497.12'
L24	S00°03'40"W	500.83'

Note: This map is specifically for use with the boundary adjustment application process. For a copy of the filed survey, see the Umatilla County Surveyor's Office.

REGISTERED PROFESSIONAL LAND SURVEYOR
 Stephen K. Haddock
 OREGON
 JULY 9, 2001
 STEPHEN K. HADDOCK
 56295LS
 RENEWS 6-30-15

BOUNDARY ADJUSTMENT SURVEY FOR
 Mr. Kent Madison
 28647 Madison Road
 Echo, Oregon 97826

LOCATION: S1, T2N AND S25 AND S36, T3N, R27E, W.M., UMATILLA COUNTY, OREGON

PROJECT DATE: DECEMBER 2012

Project No. 12-28 SCALE: 1" = 600'

WITNESS TREE SURVEYING
 Stephen K. Haddock, PLS, CFedS
 P.O. Box 6
 Pilot Rock, Oregon 97868
 (541) 443-2922

RECEIVED BY
 Umatilla County Surveyor
 Date: 12/11/2013
 Rec'd By: *[Signature]*
 No.: 13-5564c

Monuments set in May of 2013.