



LEGAL DESCRIPTION
 Commencing at a point, said point being the Southwest corner of Block 4, Lot 2 "Dees Addition" to the City of Pendleton, Section 11, Township 2 North, Range 32 East of the W.M.; thence North 89°58'30" East a distance of 191.89 feet to the True Point of Beginning for this description; thence North 00°01'30" West a distance of 249.16 feet to the South right-of-way line of Interstate 80 North; thence Northeast along the said South right-of-way line the following courses and distances: North 70°14'00" East a distance of 250.36 feet; thence North 79°30'32" East 55.90 feet; thence leaving the said South right-of-way line South 00°01'30" East a distance of 347.69 feet to the North right-of-way line of County Road No. 537; thence along the North right-of-way line of County Road No. 537 South 89°58'30" West a distance of 289.77 feet to the True Point of Beginning; All being in the County of Umatilla, State of Oregon.

LEGEND:

- denotes found 3/8 in iron pin
- () denotes platted information

NOTE: Bearings based on ties to "Dees Addition" to the City of Pendleton, Oregon.
 Elevations are U.S.G.S. Sea Level Datum.

No street lights in area except as shown.
 See attached drawings for water, sewer, streets, storm sewers.

SEC 11 T2N R32E



KRUMBEIN ENGINEERING CO.
 ENGINEERS - SURVEYORS - PLANNERS
 221 S. Main, Pendleton, Oregon

Survey for
MOTEL - G
 Pendleton, Oregon Site #348

SCALE 1" = 20'
 DATE Aug 1, 1978
 DWN BY JLS
 CRD BY JPS
 DRWG NO. 18-350

VICINITY MAP
 n.t.a.