

GPS CONTROL STATION

OREGON STATE PLANE, NORTH ZONE

STATION NAME: 104	GEODETIC COOR: NAD 83(91):
SECTION: NW 1/4, S23, T.2N., R.32E., UMATILLA COUNTY, OREGON	LAT: 45° 38' 43.45386" N LONG: 118° 47' 11.81406" W
DATE SET: EXISTING MONUMENT	STATE PLANE CO-ORDINATES, NAD 83-91, INT.FT.:
SURVEYOR: WILLIAM R. WELLS PLS 1106	N: 726049.349 E: 8640256.752 THETA: 1° 12' 54.39"
FIRM: WILLIAM R. WELLS, LAND SURVEYING AND PLANNING P.O. BOX 1696 PENDLETON, OR 97801 (541) 276-6362	SCALE FACTOR: 0.99992917 ELEV: 1208.28 US.FT. ELEV. DATUM: LOCAL, CITY OF PENDLETON
ORDER: SECOND ORDER, CLASS I	CITY OF PENDLETON CO-ORDINATES INT.FT.:
	N: 41679.739 E: 47805.217

LOCATION:

TRAVEL SOUTH ON TUTUILLA CREEK ROAD 1500 FEET M/L SOUTH OF INTERSECTION OF TUTUILLA CREEK ROAD AND S.W. ATHENS AVENUE TO EAST-WEST FENCELINE EAST OF ROAD. FOLLOW FENCELINE EAST 400 FEET M/L AND THEN SOUTH 2 FEET M/L TO STATION.

STATION IS A 2 INCH BRASS DISK ON AN IRON PIPE MARKED "CITY OF PENDLETON", ABOUT 8 INCHES BELOW GROUND SURFACE.

STATION IS THE NORTHWEST CORNER OF SECTION 23, AND IS REFERENCED BY RECORDED CORNER CERTIFICATE.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Renews 6-30-96