

HORIZONTAL CONTROL DATA

OREGON STATE PLANE, NORTH ZONE (3601)

STA. NAME: 9331

QUARTER SECTION: SE

GEODETIC COOR: NAD 83(91)

SEC. 23 TWP.4 N,RGE.28E
UMATILLA CO.ORE.

LAT: 45°48'21.55794" N

DATE SET: JULY ,1993

LONG: 119°16'31.20742" W

SURVEYOR: WALTER L. CASWELL
PLS 737

SP. COOR: NAD 83(91)

N: 782324.165 INT.FT.

FIRM: EAGLE GPS SURVEY CORP
13545 NW SCIENCE PARK DR
PORTLAND, OR. 97229
(503) 643-1073

E: 8514402.194 INT.FT.

THETA: 0°52'06.654"

TYPE: GPS

SCALE FACTOR: 0.999956461

ORDER: SECOND, CLASS: 1

ELEV: 644.287 US.FT.

ELEV. DATUM: NGVD 29

DIRECTIONS "TO REACH"

FROM INTERSECTION OF FEEDVILLE RD. AND OTT RD., GO 1.2 MILE WEST
ON FEEDVILLE ROAD, AND THEN 25 FEET NORTH FROM CENTERLINE OF
FEEDVILLE ROAD TO MONUMENT.

STATION IS A 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP
INSCRIBED "BUFORD ASSOC. PLS 1148".

STATION IS 25 FEET NORTH FROM CENTERLINE OF FEEDVILLE ROAD.

METERS X 3.28083333333 = U.S. FEET
METERS X 3.28083989501 = INTERNATIONAL FT.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Walter L. Caswell

OREGON
JULY 8, 1966
WALTER L. CASWELL
737

Exp. 12/31/93