

HORIZONTAL CONTROL DATA

OREGON STATE PLANE, NORTH ZONE (3601)

STA. NAME: 9336

QUARTER SECTION: NW

GEODETIC COOR: NAD 83(91)

SEC. 25 TWP.4 N,RGE.28E
UMATILLA CO.ORE.

LAT: 45°48'12.19042" N

DATE SET: JULY ,1993

LONG: 119°15'55.27933" W

SURVEYOR: WALTER L. CASWELL
PLS 737

SP. COOR: NAD 83(91)

FIRM: EAGLE GPS SURVEY CORP
13545 NW SCIENCE PARK DR
PORTLAND, OR. 97229
(503) 643-1073

N: 781414.183 INT.FT.

E: 8516961.508 INT.FT.

THETA: 0°52'32.133"

TYPE: GPS

SCALE FACTOR: 0.999955955

ORDER: SECOND, CLASS: 1

ELEV: 633.234 US.FT.

ELEV. DATUM: NGVD 29

DIRECTIONS "TO REACH"

FROM INTERSECTION OF S.W. HIGHLAND AVE. AND HWY. 395 IN
HERMISTON, GO SOUTHEAST ON HWY. 395 3.0 MILE TO FEEDVILLE ROAD,
THEN WEST ON FEEDVILLE ROAD 1.0 MILE TO A PAVED SIDE ROAD TO THE
NORTH, THEN CONTINUING ON FEEDVILLE ROAD 0.15 MILE TO A PATH (100
FEET WEST OF MILE POST 24), THEN SOUTH 0.1 MILE TO A FORK IN PATH
AND EDGE OF CANAL, THEN EAST 0.15 MILE TO MONUMENT.
STATION IS A 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP
INSCRIBED "BUFORD ASSOC. PLS 1148".

STATION IS 0.2 MILE SOUTH OF INTERSECTION OF FEEDVILLE AND PAVED
CROSS ROAD THAT IS 1.0 MILE WEST OF 395 AND FEEDVILLE INT. AT
BEND OF CANAL ON NORTH SIDE. FROM INTERSECTION OF CROSS ROAD AND
FEEDVILLE, GO WEST 0.15 MILE TO TRACK ROAD ON RIGHT, THEN SOUTH
0.1 MILE TO FORK AND CANAL, THEN EAST 0.15 MILE TO MONUMENT.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Walter Caswell

OREGON
JULY 8, 1966
WALTER L. CASWELL
737

Exp. 12/31/93

METERS X 3.28083333333 = U.S. FEET
METERS X 3.28083989501 = INTERNATIONAL FT.