

HORIZONTAL CONTROL DATA

OREGON STATE PLANE, NORTH ZONE (3601)

STA. NAME: 9327

QUARTER SECTION: NW

GEODETIC COOR: NAD 83(91)

SEC. 27 TWP.4 N,RGE.28E
UMATILLA CO.ORE.

LAT: 45°48'21.89848" N

DATE SET: JULY ,1993

LONG: 119°18'32.24603" W

SURVEYOR: WALTER L. CASWELL
PLS 737

SP. COOR: NAD 83(91)

FIRM: EAGLE GPS SURVEY CORP
13545 NW SCIENCE PARK DR
PORTLAND, OR. 97229
(503) 643-1073

N: 782230.471 INT.FT.

E: 8505828.391 INT.FT.

THETA: 0°50'40.815"

TYPE: GPS

SCALE FACTOR: 0.999956479

ORDER: SECOND, CLASS: 1

ELEV: 592.883 US.FT.

ELEV. DATUM: NGVD 29

DIRECTIONS "TO REACH"

FROM THE INTERSECTION OF FEEDVILLE ROAD AND HERMISTON-HINKLE ROAD, GO WEST .85 MILE TO MILE POST 26 OF UMATILLA COUNTY. THEN, GO 15 FEET SOUTH OF CENTERLINE OF FEEDVILLE ROAD.

STATION IS A 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP INSCRIBED "BUFORD ASSOC. PLS 1148".

STATION IS 15 FEET SOUTH OF CENTERLINE OF FEEDVILLE ROAD, 10 FEET NORTH OF BARB WIRE FENCE.

METERS X 3.2808333333 = U.S. FEET
METERS X 3.28083989501 = INTERNATIONAL FT.

