

HORIZONTAL CONTROL DATA

OREGON STATE PLANE, NORTH ZONE (3601)

STA. NAME: 9303

QUARTER SECTION: SE

GEODETIC COOR: NAD 83(91)

SEC. 10 TWP.5 N,RGE.28E
UMATILLA CO.ORE.

LAT: 45°55'25.13904" N

DATE SET: JULY ,1993

LONG: 119°17'24.35461" W

SURVEYOR: WALTER L. CASWELL
PLS 737

SP. COOR: NAD 83(91)

FIRM: EAGLE GPS SURVEY CORP
13545 NW SCIENCE PARK DR
PORTLAND, OR. 97229
(503) 643-1073

N: 825167.815 INT.FT.

E: 8509995.216 INT.FT.

THETA: 0°51'28.962"

TYPE: GPS

SCALE FACTOR: 0.999981483

ORDER: SECOND, CLASS: 1

ELEV: 490.593 US.FT.

ELEV. DATUM: NGVD 29

DIRECTIONS "TO REACH"

FROM THE NORTHWEST CORNER OF MCNARY GOLF COURSE, AT INTERSECTION
OF KALAMA AVE. AND WILLAMETTE AVE. (N.E. OF SAID INTERSECTION),
GOLF COURSE IS ACCESSIBLE FROM HWY. 730 AND MCNARY BEACH ACCESS
ROAD.

STATION IS A 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP
INSCRIBED "BUFORD ASSOC. PLS 1148".

STATION IS 30 FEET NORTH OF THE CENTERLINE OF KALAMA AVE., 40
FEET EAST OF THE CENTERLINE OF WILLAMETTE AVE.

METERS X 3.28083333333 = U.S. FEET
METERS X 3.28083989501 = INTERNATIONAL FT.

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Walter L. Caswell
OREGON
JULY 8, 1966
WALTER L. CASWELL
737
Exp. 12/31/93