

TOMKINS LAND SURVEYING, INC.
20 EAST POPLAR, SUITE 204
WALLA WALLA WA 99362
PHONE: 509/522-4843
FAX 509/522-1902
email: tomkins@wwics.com

JUNE 17, 1998

HORIZONTAL CONTROL DATA

STA. NAME: 924

LOCATION: TOWNSHIP 5 NORTH, RANGE 35 EAST, WILLAMETTE MERIDIAN. S.W. 1/4 OF SECTION 23.

DESCRIPTION: 3" BRASS DISC SET IN CONCRETE ON THE BANK EAST OF THE EASTERLY EDGE OF STEEN ROAD NEAR THE SOUTH 1/4 CORNER OF SECTION 23. USGS BENCH MARK S-80

GEODETIC COORDINATE: NAD 83(91)

LAT: 45°53'21.77799" N.

LONG: 118°24'14.04162" W.

STATE PLANE COORDINATE: NAD 83(91) OREGON NORTH ZONE (3601)

N: 249110.112 METERS

E: 2662671.525 METERS

N: 817290.394 INT. FEET

E: 8735798.980 INT. FEET

ELEVATION: 393.83 METERS

1292.11 FEET

ELEVATION DATUM: NAVD 88

THETA: 1°29'11.5"

GRID FACTOR: 0.999973756

SEA LEVEL FACTOR: 0.999938198

COMBINED SCALE FACTOR: 0.999911956

CONVERSION:

METERS X 3.28083333333 = U.S. FEET

METERS X 3.28083989501 = INTERNATIONAL FEET

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Greg E. Flowers

OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/99

6/17/98