

Bonneville Power Administration
Geodetic Control Data Sheet

Station: WM010 (210)
 Project: Wallula-Smiths Harbor-McNary
 Section: SW 1/4 31 Township: 8 North Range: 32 East Meridian: Willamette
 County: Walla Walla State: WA USGS Quad: Slater, Washington
 Surveyor: M R Heidecke Date Surveyed: July, 2001

Instrument:

The horizontal coordinates and orthometric elevation were established by GPS observations using six Trimble 4000 SSI dual frequency receivers with Compact L1/L2 antennae with ground plane.

Adjustment:

The Basis of Coordinates for this survey is the Washington State Coordinate System, South Zone, NAD 83 (1998). The horizontal component of the least squares adjustment was constrained by holding NGS Stations B 340 (A), B 502 (B), PENDLETON (B), STANFIELD EAST BASE RESET (B), and BURDEN (B). The vertical component of the least squares adjustment was constrained by holding NGS Benchmarks B 340 (First Order Class II), B 502 (First Order Class II), BURDEN (Second Order Class II), V 203 (Second Order Class 0), G 640 (First Order Class I). The elevation for point 106, 201, 249, and 255 were determined by differential leveling from G 640, D 502, E 525 and F 431 respectively and held.

Horizontal Datum: NAD83 (1998) Linear Unit: U.S. Survey Feet
 Vertical Datum: NAVD88 Linear Unit: U.S. Survey Feet

Latitude: N 46-07-46.55518	Longitude: W 118-51-28.39772
US State Plane Coordinate System:	Washington South Zone - 4602
Northing: 294,702.604	Easting: 2,056,721.823
Orthometric Elevation: 602.98	Ellipsoid Height: 532.17
Combined Factor: 0.99992062	Convergence: - 1-11-34
Confidence: 95% Confidence ("1.96 Sigma") Values	
Northing-0.011	Easting-0.008 Elevation-0.102

Monumentation: BPA 3/4-inch Aluminum Cap on 5/8-inch aluminum rod, flush with ground.
 Stamping: U.S.D.O.E. Bonneville Pwr. Adm., WM010 - FEC-01 - ATB - GPS

To-Reach Description:

Begin at Wallula Post Office at Wallula, Wa. 99363. Drive north on Columbia Way (County Road #1870) 0.2 miles to intersection of Columbia Way and Washington State Highway #12. Drive north on Washington State Highway #12, 3.8 miles to intersection of Highway #12 and Dodd-Iowa Beef Road. Turn right and drive east on Dodd-Iowa Beef Road 4.6 miles to the crossing of BPA Lower Monumental-McNary 500kV transmission line. Drive southerly on the transmission line access road 1.1 miles to intersection of a dirt field road along the north side of a canal running east-west along the south section line of Section 31, Township 8 North, Range 32 East. Drive west on dirt road 0.5 miles to intersection of a dirt field road. Drive north on the dirt field road 0.3 miles to the station. Station is 35 feet west of centerline of dirt road. Witness post is a yellow carsonite marker inscribed with BPA logo, bearing and distance to station.

RECEIVED BY
 Washtenaw County Survey
 Date _____
 Rec'd By _____
 02-19-9