

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 03/19/20.

CORNER DESIGNATION: A-13, The Northeast corner of Section 4, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set post for corner to Secs. 3, 4, 33 and 34, drove charred stake and raised mound with trench as per instructions.

MONUMENT AND ACCESSORIES FOUND: Found a 4 1/2' diameter stone mound. There are no other nearby possessory features, and no other stones.

MONUMENT MARKING DETAIL:

T2N R31E  
S33|S34  
-----  
S4|S3  
T1N  
2020  
54657PLS

MONUMENT SET: At the center of the stone mound, set a 5/8 by 30" rebar 24" in the ground and capped with a 2" aluminum cap marked as shown in the Monument Marking Detail. Surrounded new monument with stones. Placed a Witness sign in the stone corner mound.

New accessories:

- A 5/8 by 18" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 41°31' E, 28.3'.
  - A 5/8 by 18" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 44°48' E, 35.7'.
  - A 5/8 by 18" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 42°02' W, 29.9'.
  - A 5/8 by 18" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 21°57' W, 32.8'.
- Attached bearing object signs to the rebar accessories.

Bearings to corner accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner falls on a West facing hillside.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 709710.09  
E: 8603120.05

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

Surveyor's Seal

\1N31A-13



RENEWS: 6:30:20

20-043-C