

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 03/19/20.

CORNER DESIGNATION: A-15, The North One-Quarter corner of Section 3, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set post for 1/4 Sec. Cor., drove charred stake and raised mound with trench as per instructions.

MONUMENT AND ACCESSORIES FOUND: Found a 3' diameter stone mound. There are old fencing stone mounds extending Southerly toward a standing fence angle point on the top of a ridge.

**MONUMENT MARKING DETAIL:**

T~~2~~N R31E  
S34  
1/4 -----  
S3  
T1N  
2020  
54657PLS

MONUMENT SET: At the center of the found stone mound, set a 2 1/2" brass cap on 1 1/4 by 30" galvanized iron pipe 24" in the ground and surrounded with a 3' earth and stone collar. Brass cap is marked as shown in Monument Marking Detail. Placed a Witness sign in the stone and earth corner mound.

**New accessories:**

A 5/8 by 18" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 77°21' E, 29.4'.  
A 5/8 by 18" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 25°32' E, 32.4'.  
A 5/8 by 18" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 57°56' W, 28.6'.  
A 5/8 by 18" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 12°40' W, 28.5'.  
Attached bearing object signs to the rebar accessories.  
Bearings to corner accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner falls on a West facing slope.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 709745.91  
E: 8605724.68

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

Surveyor's Seal

\1N31A-15



RENEWS: 6 : 30 : 20

20-043-C