

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 03/26/20.

CORNER DESIGNATION: C-21, The East One-Quarter corner of Section 2, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set a post for 1/4 Sec. Cor., drove charred stake and raised mound with trench as per instructions. In Survey No. 115, in January, 1900, John Kimbrell, County Surveyor, reestablished this corner and set a 24 by 16 by 10" stone in a mound of stone. Survey No. 115 is found in the Record of Private Surveys Books.

MONUMENT AND ACCESSORIES FOUND: None. Found a old rock crib with old fences North and West. The crib is filled with stones including one loose stone, broke in two pieces. The two stone pieces match the record stone size but no marks were found. I accept the Southeast corner of the old rock crib as the corner point.

MONUMENT MARKING DETAIL:

T1N R31E
1/4
S2|S1
2020
54657PLS

MONUMENT SET: At the accepted corner point at the Southeast corner of the rock crib, set a 5/8 by 24" pointed rebar in a hole drilled into rock on a rocky hillside. The rebar is capped with a 2" aluminum cap marked as shown in Monument Marking Detail. Surround the corner monument with earth and stones. Nailed a Witness sign to wood post in rock crib Northwest of the corner point.

New accessories:

A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 01°26' W, 78.8', in old down fence.

A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 03°23' W, 23.9', in old down fence.

A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 70°01' W, 80.5'.

A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 71°27' W, 87.2'.

Wired bearing object signs to the rebar accessories.

Bearings to accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner falls on a very rocky South facing hillside at an old fence corner.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 707135.18

E: 8613726.52

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\IN31C-21

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Jason M. Wells
OREGON
NOVEMBER 29, 2010
JASON M. WELLS
54657PLS

RENEWS: 6/30/20

20-043-C