

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 03/26/20.

CORNER DESIGNATION: E-13, The Southeast corner of Section 4, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under contract No. 92 dated September 12, 1860. Notes state: Set post for Sec's. 3, 4, 9 and 10, drove charred stake and raised mound with trench as per instructions. Willard Bradley, County Surveyor, in his County Survey No. 411, dated April, 1916, surveyed through this corner but did not recover it. Survey No. 411 is found in the Record of Private Survey Books.

MONUMENT AND ACCESSORIES FOUND: None. The area has been farmed in the past. The soil around the corner area is shallow.

MONUMENT MARKING DETAIL:

T1N R31E  
S4|S3  
-----  
S9|S10  
2020  
54657PLS

MONUMENT SET: I reestablished this corner by double proportion measurement holding the East 1/4 corner of Section 9 and Northeast corner of Section 4 for latitude and the North 1/4 corner of Section 9 and Northeast corner of Section 10 for departure. At the reestablished corner point, set a 5/8 by 24" pointed rebar in a drilled hole into the rock, and capped with a 2" aluminum cap, marked as shown in Monument Marking Detail. The aluminum cap is 1" above ground line and the monument is surrounded with stones. Set a steel fence post 2 1/2' North of corner and attached Witness sign.

New accessories:

- A silver Deep-1 magnet bears N 35°43' E, 26.3'.
  - A purple Deep-1 magnet bears S 45°31' E, 26.9'.
  - A blue Deep-1 magnet bears S 47°42' W, 33.2'.
  - A orange Deep-1 magnet bears N 61°28' W, 54.9'.
- Buried bearing object signs with the Deep-1 magnets which are buried 18" below ground line.  
Bearings to accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner falls on Northeast facing hillside about 50' North of a old farm road.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 704322.73  
E: 8603273.59

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

Surveyor's Seal

\1N31E-13



RENEWS: 6/30/20

20-043-C