

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 03/26/20.

CORNER DESIGNATION: E-15, The North 1/4 corner of Section 10, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under contract No. 92 dated September 12, 1860. Notes state: Set post for 1/4 Sec. Cor., drove charred stake and raised mound with trench as per instructions. Willard Bradley, County Surveyor, in his County Survey No. 411, dated April, 1916, surveyed through this corner but did not recover it. Survey No. 411 is found in the Record of Private Survey Books.

MONUMENT AND ACCESSORIES FOUND: None. The area has been farmed in the past and is presently a CRP field.

MONUMENT MARKING DETAIL:

T1N R31E
S3
1/4 -----
S10
2020
54657PLS

MONUMENT SET: I reestablished this corner on the parallel of latitude by single proportion measurement between the Northeast and Northwest corners of Section 10. At the reestablished corner position, set a 2 1/2" brass cap on 1 1/4 by 30" galvanized iron pipe 27" in the ground. Cap is marked as shown in Monument Marking Detail. Set a steel fence post 2' North of the corner and attached Witness sign.

New accessories:

- A silver Deep-1 magnet bears N 55°59' E, 26.9'.
 - A purple Deep-1 magnet bears S 34°57' E, 28.0'.
 - A blue Deep-1 magnet bears S 46°48' W, 31.4'.
 - A orange Deep-1 magnet bears N 41°11' W, 27.1'.
- Buried bearing object signs with the Deep-1 magnets which are buried 18" below ground line.
Bearings to accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner falls on a Northeast facing hillside in a previously farmed area which is presently a CRP field.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 704365.74
E: 8605900.06

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\1N31E-15



RENEWALS: 6:30:20

20-043-C