

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 03/26/20.

CORNER DESIGNATION: E-21, The Northeast corner of Section 11, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set a post for corner to Sec's. 1, 2, 11 and 12, raised stone mound as per instructions. This corner was recovered by John Kimbrell, County Surveyor, in his January, 1900 Survey No. 115. Kimbrell does not state what was found for the corner. The corner was recovered by E.C. Macomber, County Surveyor, in his June, 1902 Survey No. 141. Macomber calls the corner as a stone mound on a point of basalt rock. John Kimbrell, County Surveyor, in his January, 1909 Survey No. 274, recovers the corner but does not state what was found. Old Surveys 115, 141 and 274 are found in the Record of Private Survey Books. W.E.O. Criger in his 1953 Survey No. Q-53-B, calls this corner as a "Stone and 2" iron pipe, 18" above ground marks". Dave Krumbein, in his 1993 Partition Plat No. 1994-03, recovers a "2" O.D. iron pipe and stone as called for by Criger".

MONUMENT AND ACCESSORIES FOUND: I find and hold a 2 1/2" O.D. galvanized iron pipe, solidly set in a 3 1/2' diameter stone mound. The pipe has a wood hub in it for the measure point.

MONUMENT MARKING DETAIL:

T1N R31E  
S2|S1  
-----  
S11|S12  
2020  
54657PLS

MONUMENT SET: I hold the pipe as the corner monument and wire a 1 1/2" aluminum disk marked "Wells Surveying 54657PLS", to the pipe.

I add the following new accessories:

- A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 76°24' E, 15.4'.
  - A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 55°21' W, 31.0'.
  - A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 82°04' W, 26.7'.
  - A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 13°52' W, 60.5'.
- Wired bearing object signs to the new accessories. Placed a Witness sign in the stone mound, South of the corner pipe.

Bearings to accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner is located on a point of basalt rock North of Coombs Canyon and Coombs Canyon Road and West of Ranch Road.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 704497.85  
E: 8613801.00

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

Surveyor's Seal



RENEWS: 6:30:20

\N31E-21

20-043-C