

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 03/27/20.

CORNER DESIGNATION: E-5, The Southeast corner of Section 6, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set a post for corner to Sec's., 5, 6, 7 and 8, drove charred stake and raised mound with trench as per instructions. Willard Bradley, County Surveyor, surveyed through this corner on his April, 1916 Survey No. 411. Bradley did not recover the corner. Survey No. 411 record is found in the Record of Private Survey Books.

MONUMENT AND ACCESSORIES FOUND: I accept a fence corner with old fences extending North, South, East and West as best remaining evidence of the original corner position. The corner area is very rocky.

MONUMENT MARKING DETAIL:

T1N R31E  
S6|S5  
-----  
S7|S8  
2020  
54657PLS

MONUMENT SET: At the corner point, set a 5/8 by 15" rebar in hole drilled into rock and capped with a 2" aluminum cap marked as shown in Monument Marking Detail. Nailed a Witness sign to a wood corner post in fence, West of the corner point.

New accessories:

- A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 28°57' E 37.2'.
  - A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 85°05' E 20.2'.
  - A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 83°44' W 20.9'.
  - A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 54°23' W 35.6'.
- Wired bearing object signs to the rebar accessories.  
Bearings to accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner is located at an old fence intersection on a very rocky South facing slope.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 704200.99  
E: 8592798.72

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

Surveyor's Seal

\1N31E-5



RENEWS: 6/30/20

20-043-C