

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 03/27/20.

CORNER DESIGNATION: E-7, The South One-Quarter corner of Section 5, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set a post for 1/4 Sec. Cor., drove charred stake and raised mound with trench as per instructions. Willard Bradley, County Surveyor, in his April, 1916 Survey No. 411, surveyed through this corner but did not recover it. Survey No. 411 record is found in the Record of Private Survey Books.

MONUMENT AND ACCESSORIES FOUND: None. Accepted fence corner with fences North and East as best remaining evidence of the original corner position. There is evidence of fencing (old rock mounds), extending South from the corner point.

MONUMENT MARKING DETAIL:

T1N R31E
S5
1/4 -----
S8
2020
54657PLS

MONUMENT SET: At the accepted corner position, set a 5/8 by 24" pointed rebar in a hole drilled into solid rock on the South side of fence corner. Set a 2" aluminum cap, marked as shown in Monument Marking Detail on the corner rebar, and surrounded with a mound of stone. Nailed a Witness sign to the wood fence corner post just North of the corner.

New accessories:

A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 88°52' E, 28.9'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 01°00' E, 40.1'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 77°04' W, 36.0'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 02°45' W, 27.5'.
Wired bearing object signs to the rebar accessories.
Bearings to accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner is located on a South facing hillside at a fence corner with fences North and East. The corner area is very rocky.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 704203.98
E: 8595418.33

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\1N31E-7



RENEWS: 6/30/20

20-043-C