

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 04/03/20

CORNER DESIGNATION: G-13, The East One-Quarter corner of Section 9, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set post for 1/4 Sec. Cor., drove charred stake and raised mound with trench as per instructions.

MONUMENT AND ACCESSORIES FOUND: Found and accepted a 3 1/2' diameter mound of small stones, 10' North of newer East-West fence line, and about 30' East of farm road and gate.

MONUMENT MARKING DETAIL:

T1N R31E
1/4
S9|S10
2020
54657PLS

MONUMENT SET: At the center of the found stone mound, Set a 5/8 by 18" rebar in hole drilled in rock and capped with a 2" aluminum cap marked as shown in Monument Marking Detail. The top of the rebar is about 6" above ground line and is surrounded with a mound of earth and stone. Wired a Witness sign to an existing fence post in the existing fence line about 15' SE of corner monument.

New accessories:

A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 79°08' E, 39.3'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 65°36' E, 18.5'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 53°46' W, 13.4'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 71°51' W, 26.9'.
Rebar accessories are set in existing East-West fence line. Wired bearing object signs to the rebar accessories.

Bearings to accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner falls 10' North of an East-West fence line and about 30' East of a farm road and gate.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 701687.17
E: 8603324.60

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\1N31G-13



RENEWS: 6/30/20