

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 02/24/20

CORNER DESIGNATION: G-21, The East One-Quarter corner of Section 11, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set post for 1/4 sec.cor. , drove charred stake and raised mound with trench as per instructions. The corner area was surveyed through by John Kimbrell in his Survey No. 274 found in Record of Private Survey books. Kimbrell computed but did not reestablish this corner. Kimbrell set a pipe for the 1/16 th corner North of this corner. I searched but did not recover the pipe. There is old fence evidence extending West from the computed position for the pipe 1/16 th corner.

**MONUMENT AND ACCESSORIES FOUND:**

Found and held position of two stones in North-South fence line at the correct distance per Survey No. 274 from the pipe found at the Northeast corner of Section 11. Areas East and West of the found stones in North-South fence have been farmed.

**MONUMENT MARKING DETAIL:**

T1N R31E  
1/4  
S11|S12  
2020  
54657PLS

MONUMENT SET: At position midway between the found stones, set a 2 1/2" brass cap on 1 1/4 by 30" galvanized iron pipe 30" in the ground with the two stones alongside. Cap is marked as shown in Monument Marking Detail.

**New accessories:**

A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears North, 19.0'.

A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears South, 9.3'.

A orange Deep-1 magnet bears N 57° W, 15.8'.

A blue Deep-1 magnet bears S 69° W, 13.7'.

Placed bearing object signs beside Deep-1 magnets, which are buried 18" below ground. Wired bearing object signs to the rebar accessories in the North-South fence line. Wired a Witness sign to existing steel fence post in fence 4' North of monument. Used steel tape and Brunton pocket transit with 14° East declination to measure corner accessories.

LOCATION AND COMMENTS: Corner is located in a North-South fence line about 1500' South of Coombs Canyon Road.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 701864.67

E: 8613884.18

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

Surveyor's Seal

\N31G-21



RENEWS: 6/30/20

20-043-C