

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 02/28/20.

CORNER DESIGNATION: J-15, The North One-Quarter corner of Section 15, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set post for 1/4 sec.cor ., drove charred stake and raised mound with trench as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. I reestablished this corner on the parallel of latitude between the Northeast and Northwest corners of Section 15, holding the Northerly projection of an old fence berm, (no fence remains), for departure.

MONUMENT MARKING DETAIL:

T1N R31E
S10
1/4 -----
S15
2020
54657PLS

MONUMENT SET:

At the reestablished corner position, set a 5/8 by 18" rebar in hole drilled in rock. Placed a 2" aluminum cap on rebar and surrounded with a few stones. The aluminum cap is at ground level and is marked as shown on Monument Marking Detail. Wired a Witness sign to a rock in the monument mound.

New accessories:

A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 50°57' E, 30.0'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 51°11' E, 37.4'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 45°01' W, 35.6'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 37°27' W, 31.1'.
Wired bearing object signs to the rebar accessories.
Bearings to accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner is on a East facing slope about 300' West of Redwine Road.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 699098.19
E: 8605971.28

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\IN31J-15

