

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 03/04/20.

CORNER DESIGNATION: J-21, The Northeast corner of Section 14, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set post for corner to Sec's. 11, 12, 13 and 14 drove charred stake and raised mound with trench as per instructions. This corner was recovered by County Surveyor John Kimbrell in Record of Private Surveys No. 274 and 276, in 1909. Kimbrell recovers the corner but does not state what was found.

MONUMENT AND ACCESSORIES FOUND: Accepted fence corner with old fences extending North, East and South as best remaining evidence of the original corner point. The fence to the South is evidenced by old fencing stones with wire tied to them. There is a gate post 15' +/- West with a fence extending South from it.

MONUMENT MARKING DETAIL:

T1N R31E
S11|S12

S14|S13
2020
54657PLS

MONUMENT SET: Set a 5/8 by 18" rebar in a hole drilled in rock and capped with a 2" aluminum cap marked as shown in monument marking detail. The aluminum cap is 5" above ground and is surrounded with a stone collar.

New accessories:

A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 63° 51' W, 43.2'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 81° 30' W, 31.8'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 42° 58' W, 23.9'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 22° 58' W, 41.4'.
Wired bearing object sign to each rebar accessory. Nailed a Witness sign to wood fence corner post just North of corner monument.

Bearings to corner accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner falls on a South sloping hillside in very rocky ground. There are numerous rock piles from cleaning up the farmed fields around the corner.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 699207.06
E: 8613882.20

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\1N31J-21



RENEWS: 6:30:20

20-043-C