

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 03/04/20

CORNER DESIGNATION: J-9, The Southeast corner of Section 8, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set post for corner to Secs, 8, 9, 16 and 17 drove charred stake and raised mound with trench as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. The corner area has been farmed and is now in the CRP. Reestablished corner position by double proportion measurement holding the Southeast corner of Section 17 and the East 1/4 corner of Section 8 for latitude and the old existing fence line along the West line of the East Half of the East Half of Section 17 and the Southerly fence projection on the North-South centerline of Section 9 for departure.

**MONUMENT MARKING DETAIL:**

T1N R31E  
S8|S9  
-----  
S17|S16  
2020  
54657PLS

MONUMENT SET: A the reestablished corner position, set a 2 1/2" brass cap on 1 1/4 by 30" galvanized iron pipe 24" in the ground marked as shown in Monument Marking Detail.

**New accessories:**

- A silver Deep-1 magnet bears N 53°16' E, 34.6'.
- A purple Deep-1 magnet bears S 30°50' E, 35.9'.
- A blue Deep-1 magnet bears S 56°20' W, 34.7'.
- A orange Deep-1 magnet bears N 37°13' W, 27.3'.

Buried bearing object signs with the Deep-1 magnets which are buried 18" below ground line. Set a steel fence post 2' South of corner monument with Witness sign attached. Bearings to accessories are State Plane Grid bearings.

LOCATION AND COMMENTS: Corner is located in a CRP field on a North facing slope about 1200' South of Coombs Canyon Road.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 698907.97  
E: 8598072.75

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

Surveyor's Seal

\1N31J-9



RENEWS: 6/30/20