

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 02/28/20.

CORNER DESIGNATION: N-11, The South One-Quarter corner of Section 16, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set a post for 1/4 Sec. Cor., drove charred stake and raised mound with trench as per instructions.

MONUMENT AND ACCESSORIES FOUND: Found and held 3 1/2' diameter stone mound on rocky South facing hillside.

MONUMENT MARKING DETAIL:

T1N R31E
S16
1/4 -----
S21
2020
54657PLS

MONUMENT SET: At the center of the found stone mound, set a 5/8 by 24" pointed rebar into 14" deep hole drilled in rock in the mound. Placed a 2" aluminum cap on the rebar and surrounded the monument with stones. Aluminum cap is marked as shown in Monument Marking Detail. Placed a Witness sign in the rock mound near the corner monument.

New accessories:

A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 14° E, 31.0'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 49° E, 33.3'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 28° W, 24.6'.
A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 60° W, 28.7'.
Rebar accessories are driven to refusal on rocky hillside. Wired bearing object signs to the rebar accessories. Used steel tape and Brunton pocket transit with 14° East declination to measure accessories.

LOCATION AND COMMENTS: Corner is located on a rocky, South facing hillside. There is a dirt farm road about 1/4 mile to the East.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 693779.49
E: 8600783.73

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\1N31N-11



RENEWS: 6/30/20

20-043-C