

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 02/20/19.

CORNER DESIGNATION: N-19, The South One-Quarter corner of Section 14, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set a post for 1/4 Sec. Cor., drove charred stake and raised mound with trench as per instructions.

MONUMENT AND ACCESSORIES FOUND: Accepted fence corner with fences West and South as best remaining evidence of original corner position.

**MONUMENT MARKING DETAIL:**

~~T1N~~ R31E  
S14  
1/4 -----  
S23  
2020  
54657PLS

MONUMENT SET: At a point at the edge of a burnt fence corner post, (below ground), set a 2 1/2" brass cap on 1 1/4 by 30" galvanized iron pipe, 26" in the ground. Monument is marked as shown in Monument Marking Detail.

**New accessories:**

A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54567PLS" bears South, 11.2'  
A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54567PLS" bears South, 20.1'  
A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54567PLS" bears N 89° W, 11.0'.  
A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54567PLS" bears N 89° W, 24.6'.  
Rebar accessories are in fence lines extending South and West from the corner monument. Wired bearing object signs to all of the rebar accessories. Nailed a Witness sign to the railroad tie fence corner post South of the corner monument. Used steel tape and Brunton pocket transit with 14° East declination to measure corner accessories.

LOCATION AND COMMENTS: Corner is at fence corner intersection with fences South and West, about 250' West of Redwine Road.

**OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:**

N: 693919.13  
E: 8611345.47

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

Surveyor's Seal

\1N31N-19



RENEWS: 6:30:20

20-043-C