

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 02/28/20.

CORNER DESIGNATION: N-9, The Southeast corner of Section 17, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set a post for corner to Secs. 16, 17, 20, 21, drove charred stake and raised mound with trench as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Accepted fence corner with fences extending South and West as best remaining evidence of the original corner position.

MONUMENT MARKING DETAIL:

~~T1N~~ R31E
S17|S16

S20|S21
2020
54657PLS

MONUMENT SET: Set a 2 1/2" brass cap on 1 1/4 by 30" galvanized iron pipe 24" in the ground on North side of fence corner with fences extending South and West. Monument is marked as shown in Monument Marking Detail.

New accessories:

- A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 89°57' W, 34.2'.
- A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 88°10' W, 13.9'.
- A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 02°15' E, 14.1'.
- A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 01°39' E, 35.8'.

Wired bearing object signs to the rebar accessories. Accessories are set in wire fence lines. Bearings to accessories are State Plane Grid Bearings.

Nailed Witness sign to railroad tie fence corner post South of corner monument.

LOCATION AND COMMENTS: Corner falls at fence intersection with fences extending West and South.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 693739.36
E: 8598144.11

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\1N31N-9



RENEWS: 6:30:20

20-043-C