

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 01/07/20.

CORNER DESIGNATION: P-13, The East One-Quarter of Section 21, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set post for 1/4 Sec. Cor. drove charred stake and raised mound with trench as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. I accepted the intersection of old mounds of stone from previous fencing, extending East and North, as best remaining evidence of the original corner position. Several of the stone mounds still have fencing wire attached.

MONUMENT MARKING DETAIL:

T1N R31E
1/4
S21|S22
2020
54657 PLS

MONUMENT SET: At the intersection of old stone fencing mounds extending East and North, set a 2 1/2" brass cap on 1 1/4 by 30" galvanized iron pipe 20" in the ground to bedrock and surrounded with a 2 1/2' diameter mound of earth and stone. There is an old wire fence tie down, below ground, about 3' South of monument. Monument is marked as shown in Monument Marking Detail.

New accessories:

A 5/8" by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 21° E, 48.0', on East side of large rock.

A 5/8" by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 62° E, 44.9', on East side of large rock.

A 5/8" by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 43° E, 11.0'.

A 5/8" by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 88° W, 49.3'.

Rebar accessories have bearing object signs wired to them. Wired a Witness sign to a rock placed just South of the new corner monument. Used steel tape and Brunton pocket transit with 14° East declination to measure accessories.

LOCATION AND COMMENTS: Corner is located in a flat, rocky area, near the Southwest corner of an active CRP field.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 691141.01

E: 8603436.51

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\1N31P-13



RENEWS: 6/30/20