

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 02/21/20.

CORNER DESIGNATION: R-1, The Southwest corner of Section 19, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by David P. Thompson under Contract No. 81 dated July 8, 1859. Notes state: Set post for corner to Sec's. 24, 25, 19 & 30, and build mound of earth with pits, trench and etc., as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Accepted intersection of North-South rebuilt fence line with Easterly extension of fence line from fence corner 560' +/- West as best remaining evidence of the original corner position. The area West of corner is previously farmed and now in CRP. Area to the East is dry pasture, (previously farmed), with no previous fencing features. The existing rebuilt fence extends South for about 1/2 mile with old stone fencing mounds existing to the South.

MONUMENT MARKING DETAIL:

T1N
R30 E | R31E
S24|S19

S25|S30
2020
54657PLS

MONUMENT SET: Set a 2 1/2" brass cap on 1 1/4 by 30" galvanized iron pipe 29" in the ground in a North-South fence line. Monument is marked as shown in Monument Marking Detail.

New accessories:

- A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears North, 14.4'.
- A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears North, 27.0'.
- A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears South, 10.9'.
- A 5/8 by 24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears South, 24.1'.

Wired bearing object signs to the rebar accessories. Accessories are set in wire fence line. Used steel tape and Brunton pocket transit with 14° East declination to measure corner accessories. Wired Witness sign to steel fence post in fence 1 1/2' North of corner monument.

LOCATION AND COMMENTS: Corner falls in a rebuilt fence line on a bermed North-South field line.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 688357.65
E: 8587193.45

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\1N31R-1



RENEWS: 6:30:20

20-043-C