

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 02/21/20.

CORNER DESIGNATION: R-5, The Southeast corner of Section 19, Township 1 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. Notes state: Set post for corner to Sec's. 19, 20, 29 & 30 and raised stone mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: Found and held center of 4' diameter stone mound with rock mounds from previous fencing extending East, North and South.

MONUMENT MARKING DETAIL:

T1N R31E  
S19|S20  
-----  
S30|S29  
2020  
54657PLS

MONUMENT SET: At the center of the found stone mound, set a 5/8 by 24" pointed rebar 20" in the ground with 2" aluminum cap marked as shown in Monument Marking Detail. Monument is surrounded with stones.

New accessories:

- A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 01° E, 15.8'.
  - A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears East, 26.5', in old rock fencing mound.
  - A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 72° W, 22.6'.
  - A 5/8 by 15" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 49° W, 21.3'.
- The area is very rocky. Accessory rebars are 4 to 6" above ground line. Wired bearing object signs to the rebar accessories. Used steel tape and Brunton pocket transit with 14° East declination to measure corner accessories. Wired Witness sign a rock in the stone corner mound.

LOCATION AND COMMENTS: Corner falls on a rocky knob. There is an old radio tower on the top of the rock knob, North of the corner.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 688366.57  
E: 8592989.13

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

Surveyor's Seal

\1N31R-5



RENEWS: 6:30:20