

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 4/22/94

CORNER DESIGNATION: Z-23. South 1/4 corner section 36, T2N., R32E., W.M..

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. At that time Currin and Noland established a basalt stone, 12 X 10 X 10 ins., in the old mound, 8 ins. deep, marked 1/4 on N. face. Dug pits, 18 X 18 X 12 ins. E. and W. of cor. 5-1/2 ft. dist., raised earth mound 1-1/2 ft. high, 3-1/2 ft. base over it. In 1917, L.E. Wilkes recovered this corner and used it to re-establish the Southeast corner of Section 36. Wilkes 1917 surveys were made of the Diminished Boundary of the Umatilla Indian Reservation.

MONUMENT AND ACCESSORIES FOUND: None.

The corner position falls in top of culvert. Set witness corner monument North 00°00'00" East, 34.0 feet from true corner point, and a railroad spike stamped "1106." at the true corner point.

MONUMENT MARKING DETAIL:

WC | 34.00 FT
T2N | R32E
S36
1/4-----
S1
T1N R32E
1994
PLS 1106

MONUMENT SET: Re-established corner by single proportion measurement between the Southwest and Southeast corner of Section 36, using GLO record by Currin and Noland. Corner point falls on culvert. At a point North 00°00'00" East, 34.0 feet from corner point, set a 2 1/2" brass cap on a 1 1/4" X 30" galvanized iron pipe, 27" in the ground, with a mound of earth to the cap. (marked as shown in the monument detail). Set a railroad spike at true corner point, stamped "1106".


New Accessories: (referencing the true corner point):
Set steel guard post with witness post sign attached 1.0 feet West of witness corner.
A 5/8" x 30" iron pin with yellow plastic cap stamped 'OR PLS 1106-WA PLS 17372' bears South 15.00 feet, set 1.2 feet below ground.
A 5/8" x 30" iron pin with yellow plastic cap stamped 'OR PLS 1106-WA PLS 17372' bears N 31° E-37.8 feet. Set steel fence post 1.1 feet Northeast of iron pin.
A 5/8" x 30" iron pin with yellow plastic cap stamped 'OR PLS 1106-WA PLS 17372' bears S 69° W-16.0 feet, set 1.4 feet below ground.
Set steel fence post 1.0 feet Southwest of iron pin.
Attached bearing object sign to iron pins, and witness corner signs to steel fence posts.

LOCATION AND COMMENTS: Witness corner falls North of North edge County Road in an East-West fence line.


COMPASS DECLINATION: 18° East
FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Surveyor's Seal

Party Chief: Robert D. English
Notes: Robert D. English
Witness: F. Scot Munro



Will. R. Wells



renews 12-31-94