

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 10/16/06

CORNER DESIGNATION: T1N, R32E, N-13, The Northwest Corner of Section 22.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D. Chaplin, under GLO Contract No. 107, dated September 21, 1864.

Notes state: Set post for corner to Secs. 15, 16, 21 & 22 in mound of Earth with charred stake, pits, etc. as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Umatilla County Survey No. Q-59-B, in 1957, reported finding and holding a stone for this corner. The origin of the stone is unknown. Fences have been removed in the area and it has been farmed for wheat and is now in CRP. The stone was not recovered. Re-established the corner by holding the record angle and distance from certain found monuments recovered from Survey No. Q-59-B. See Survey filed concurrently with this corner record for angle and distance ties.

**MONUMENT MARKING DETAIL:**

T1N R32E  
S16|S15  
S21|S22  
2006  
PLS 1106

**MONUMENT SET:**

At reestablished corner point, set a 2" aluminum cap on a 5/8" x 24" iron rebar, with cap 12" below ground level, marked as shown in Monument Marking Detail.

**New accessories:**

- A silver deep-1 magnet, 18" below ground level, bears North 49° East, 40.0 feet.
  - A blue deep-1 magnet 18" below ground level, bears South 23° East, 31.4 feet.
  - A purple deep-1 magnet 18" below ground level, bears South 45 1/2° West, 39.4 feet.
  - An orange deep-1 magnet 18" below ground level, bears North 10° West, 33.8 feet.
- Buried bearing object tags with deep 1 magnets.

**LOCATION AND COMMENTS:**

Corner falls in a CRP field approximately 600 feet South of a fence line extending North.

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT  
Micha Engum

/IN32N13

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-06*