

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 10/10/06

CORNER DESIGNATION: T1N, R32E, N-17, The Northeast Corner of Section 22.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D. Chaplin, under GLO Contract No. 107, dated September 21, 1864.

Notes state: Set post for corner to Secs. 14, 15, 22 & 23 in mound of Earth with charred stake, pits, etc., as per instructions.

MONUMENT AND ACCESSORIES FOUND: None, falls in old State Highway 395. Survey No. H-253-B, for McKay National Wildlife Refuge in 1938, shows a calculated position for this corner, no monument was set or found on that survey. There are no features at the corner area except for the old paved State Highway.

MONUMENT MARKING DETAIL:

T1N R32E
S15|S14
S22|S23
2006
PLS 1106

MONUMENT SET:

Reestablished corner point by holding the visual centerline of old Highway 395 for departure and proportioning latitude between the previously reestablished Northeast Corner of Section 15 and the East one-quarter corner of Section 22. At reestablished corner point, set a 5/8" x 24" iron rebar, with a 2" aluminum cap, surrounded in concrete, in the old asphalt road. Cap marked as shown in Monument Marking Detail.

New accessories:

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106, WA PLS 17372", bears North 81° East, 14.4 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106, WA PLS 17372", bears South 11 1/2° East, 49.2 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106, WA PLS 17372", bears South 23 1/2° West, 54.0 feet.

A 3/4" brass washer, stamped "PLS 1106", 1 foot above ground level, in Pacific Power Pole #159002, bears North 39 1/2° West, 39.4 feet.

Nailed bearing object sign and witness sign to Pacific Power Pole. Wired bearing object signs to rebar accessories.

LOCATION AND COMMENTS:

Corner is located in the centerline of Old Highway 395, flush with old pavement surface..

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Micah Engum

/1N32N17

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-06

06-528-C