

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 10/16/06

CORNER DESIGNATION: T1N, R32E, R-11, The South One- Quarter Corner of Section 21.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D. Chaplin, under GLO Contract No. 107, dated September 21, 1864. dated January 11, 1865.
Notes state: Set stone 18 x 12 x 6 in for 1/4 Sec. cor.

MONUMENT AND ACCESSORIES FOUND: None, corner point falls in East-West County Road. County Road Notes, for Road No. 745, (now No. 1374), indicate the road survey went through the corner but no corner was called.

MONUMENT MARKING DETAIL:

T1N R32E
1 S21
4 S28
2006
PLS 1106

MONUMENT SET:

Held the intersection of visual centerline of County Road No. 1374 and a old field berm extending North as the best remaining evidence of the original corner position. At reestablished corner position, set a 2 3/8" brass cap on a 1 1/4" x 24" galvanized iron pipe, marked as shown in Monument Marking Detail, with cap buried 8" below road surface.

New accessories:

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106, WA PLS 17372", bears North 04° East, 19.4 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106, WA PLS 17372", bears South 69° East, 51.8 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106, WA PLS 17372", at base of railroad tie post, bears South 15° West, 24.3 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106, WA PLS 17372" bears North 76° West, 64.3 feet.

Attached bearing object tags to all rebar accessories. Attached witness sign to railroad tie post.

LOCATION AND COMMENTS:

Corner is located in the centerline of County Road No. 1374 (Hoeft Road) with a field berm extending North.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Micah Engum

/IN32R11

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-06