

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Cornet to Sections 34 and 35, T1N, R32E, W M.

Index: 1N 32 Z-17

History of original corner establishment:

Cornet originally set by Thompson in contract 79 dated 1858. His record reads: 80.00 Set post for corner to secs. 34 and 35 build a mound of earth as per instructions.

In 1864, Thompson established a new corner. His record reads: 80.00 Set stone, 15x10x10 ins., for corner to secs. 34 and 35.

Evidence Found: Found a beautifully chiseled 15x10x10 rounded river stone near an old fence corner. The stone is marked S2T1S, R32E, S34, S35

DIAGRAM

T1N R32E
SC

S34 | S35

S2T1SR32E
1997

PLS 852

Description of monument and accessories I established to perpetuate the original location of this corner:

At the location of the stone, I set a 1.25" x 30" galvanized iron pipe with 2.25" brass cap stamped as shown in the diagram. Buried the stone alongside the pipe. Top of monument is 6" above the ground with a collar of stone.

For references, I set four 5/8" by 24" rebars with 1.25" red plastic caps stamped ORLS 852 and WA WALS 13922 as described below:

- a power pole lies west of the corner with a Umatilla County Survey Monument sign attached;
- a rebar bears N01°51'E, 57.03 feet under a north bound fence line;
- a rebar bears S0°05'E, 38.61 feet at the base of a railroad tie in the south bound fence;
- a rebar bears S59°34'W, 66.00 feet under a north - south fence;
- a rebar bears N40°23'W, 84.87 feet under a north - south fence;

The bearings are true.

This work was done May 12, 1997, and witnessed by Stephen, Janet, Kodria, Benjamin and Joseph Haddock.

Office of _____ County of Umatilla
 State of _____, I hereby certify that the within instrument was filed
 in this office for record on the _____ day of _____, 19____.
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David L. Haddock

OREGON
JULY 18 1859
DAVID L. HADDOCK
852

RECEIVED BY
 Umatilla County Surveyor
 Date 7-97
 Rec'd By KK
 No. 97-140-C