


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

T 1N, R 34E., W.M.

Corner Code No. R-13  
Note: Monument marked as shown below

**History of original corner establishment:**

This corner was originally established by J.P. Currin and J.E. Noland, under Special Contract dated May 4, 1988. The original notes state that at the corner a basalt stone, 12" X 10" X 8" in., was set 8" in. in the ground, with a mound of stone raised over it. The record says the stone was marked with 2 notches on south and 3 notches on east edges.



Corner No.  
Compass Declination: 18.0°

**Description of corner evidence found:**

Found a stone mound in an old, down north by south fence line. Several stones are near record size but no marks were found on any of them. There is wire, apparently from an old east by west fence, located about 150 feet west of the corner point. The corner falls in shallow soil on a steep hillside, about 200 feet east of a ravine running south.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

The corner point falls on hard shelf rock where a conventional monument would not be practical. Therefore, I drove a 5/8" by 30" iron pin, with 1 1/2" alum. cap, 22" in the ground and surrounded with a mound of earth and stone. From the remonumented corner point:

- A 19" ponderosa pine bears N 0 3/4°E, 42.6 feet, scribed T1N R34E S22 BT.
- A 23" ponderosa pine bears S 87°E, 98.7 feet, scribed T1N R34E S27 BT.
- A 21" ponderosa pine bears S 39°E, 68.5 feet, scribed T1N R34E S27 BT.
- A 24" ponderosa pine bears S 4 1/2°W, 91.8 feet, scribed T1N R34E S28 BT.

There is no bearing tree convenient for reference in the Northwest quadrant.

Attached "Bearing Object" signs to each of the bearing trees.

Set steel fence post west of corner monument and attached "Witness Corner" sign.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of Dept. of Survey County of Umatilla  
State of OR, I hereby certify that the within instrument was filed in this office  
for record on the 16<sup>th</sup> day of January, 1990  
David H. Krumbrin by Kathleen K. Amberg  
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY  
Umatilla County Surveyor  
Date 1-90  
Rec'd by KA  
No. 90-12-R