

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/14/08

CORNER DESIGNATION: 1N34, R-7, The South One-Quarter Corner of Section 20.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner was established by Currin and Noland under Special Contract dated May 4th, 1887
Original notes state: Set basalt stone 16x10x8 marked 1/4 on North face for 1/4 Sec. corner and raised a mound of stone over it.
The corner was reported as recovered on John Kimbrell's Survey No. 162, in April-May, 1903.

MONUMENT AND ACCESSORIES FOUND:

Found 15x12x8 inch basalt stone marked "1/4", tipped over in a old East-West fence line.

MONUMENT MARKING DETAIL:

T1N R34E
1/4 S20
4 S29
2008
PLS 1106

MONUMENT SET:

At position of found stone, set a 2 3/8" brass cap on 1 1/4 by 22" galvanized iron pipe, 22" in the ground and surrounded with a mound of earth and stone. The original stone was placed on the South side of the mound. Monument marked as shown in monument marking detail.

New accessories:

- A 5/8"x24" iron rebar with 1 1/4" red plastic cap marked "ORPLS 1106 WAPLS 17372", 4" above ground level bears North 04° West, 27.6 feet.
 - A 5/8"x24" iron rebar with 1 1/4" red plastic cap marked "ORPLS 1106 WAPLS 17372", 4" above ground level in old fence line bears East, 30.5 feet.
 - A 5/8"x24" iron rebar with 1 1/4" red plastic cap marked "ORPLS 1106 WAPLS 17372", 4" above ground level bears South 09° East, 26.2 feet.
 - A 5/8"x24" iron rebar with 1 1/4" red plastic cap marked "ORPLS 1106 WAPLS 17372", 4" above ground level in old fence line bears North 88° West, 28.5 feet.
- Attached bearing object signs to all iron rebar. Planted a old wood fence post just North of corner monument and attached "Witness" sign.

LOCATION AND COMMENTS: Corner is located at the top of a North-South ridge in an old East-West fence line.

OREGON STATE PLANE COORDINATE, North Zone, NAD

83(CORS96)(EPOCH:2002.0000), International Feet:
N = 690316.85 Coordinates by OPUS solution position.
E = 8691394.82

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, LSIT

\1N34R7

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08

RECEIVED BY
Umatilla County Surveyor
Date 7-08
Rec'd By KK
No. 08-95-R