

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 8/25/95

CORNER DESIGNATION: V-23. South 1/4 corner Section 25, T1N., R34E., W.M. V-23

PREVIOUS RENEWALS/SURVEYS, ETC.:

Corner originally established by James P. Currin and James Noland under Special Contract dated May 04, 1887.

Surveyor General records state:

Set stone, 10 x 8 x 7 ins., 7 ins. in the ground, for 1/4 sec. cor. marked 1/4 on N. side, from which

A pine, 10 ins. in diam., bears S.25°W., 200 lks., marked 1/4 S B T.

No other tree in limits.

Raised mound of stone over it.

MONUMENT AND ACCESSORIES FOUND:

A 36" diameter ponderosa pine with "S" scribe visible on partially healed blaze inside 12 ins. overgrowth.

Corner stone and mound not found in open and flat high prairie ground. Stones are believed to have been moved and placed in fence line rock jacks nearby.

MONUMENT MARKING DETAIL:

T1N R34E
1 S25
4 S36
1995
ORLS 1639

MONUMENT SET:

At the position established by the reversed record bearing and distance (N 25° E, 200 lks - 132.0 feet) from the recovered record bearing tree set a 1 1/2" diameter x 20" long iron pipe with 2 1/2" diameter brass cap, projecting 6" with a 2 foot diameter mound of stone, marked as shown in monument marking detail.

From which:

A 10" ponderosa pine with a single blaze scribed "1/4 S 25 BT" bears N 72 1/2° E, 343.3 feet.

A 4" ponderosa pine with a double blaze scribed "X BT" bears S 62 1/2° E, 99.0 feet.

A 6" ponderosa pine with a double blaze scribed "X BT" bears N 43° W, 340.0 feet.

Each new bearing tree has a Umatilla County bearing object sign attached above the upper blaze and a brass washer marked PLS 1639 nailed to the lower blaze. The recovered record bearing tree has a Umatilla County bearing object sign attached alongside the blaze.

LOCATION & COMMENTS:

Corner falls 45 feet East of fence and 115 feet North of another fence in flat meadow.

COMPASS DECLINATION: 18° East.

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Witness: William Hanley, PLS 1639
Rodney Lewis, LSIT

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William L. Hanley
OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

RENEW 06/30/97

RECEIVED BY

Umatilla County Surveyor

Date 10-95

Rec'd By KK

No. 95-169-B