

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 1N , R 34E . , W.M.


Corner Code No. V-9

Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by Z. F. Moody, under Contract No. 145, dated April 23, 1876. Moody's survey was superseded by a survey by W. P. Curran and N. E. Noland, under Special Contract dated May 1, 1887. The Curran and Noland survey notes state that at the corner a 14 x 12 x 10 in basalt stone was set 9 ins. in the ground with a mound of stone over it. The stone was marked with 1 notch on the South and 4 notches on the East edges. From the corner stone:

- A pine, 8 ins. diam. bears N 35°W dist 87 lks marked S 29 T 1N BT.
- A pine, 6 ins. diam. bears S 79°E dist 100 lks marked R34E S33 BT.
- A pipe, 6 ins. diam. bears S 26°W dist 64 lks marked S 32 BT.
- No other tree in limits.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

A 19" ponderosa pine bears N 35°W, 57.4 feet (87 lks), with healed blaze.
Also found an 18" by 12" by 10" basalt stone, with no visible notches, lying on steep hillside about 10 feet downhill of corner point. This may be the original corner stone, sliding down the steep hillside over the years.

Description of monument and accessories established to perpetuate the original location of this corner:

At a point S 35°E, 57.4 feet from the recovered original bearing tree, set a 2 1/2" brass cap on a 1 1/4" by 30" galv. iron pipe, 20" in the ground and surrounded with a mound of earth and stone. Placed suspected corner stone in the new mound on the east side of the new monument. From the re-established corner point, I mark new bearing trees as follows:

- A 16" douglas fir bears N 28 1/2°E, 17.9 feet, scribed T1N R34E S28 BT.
- A 11" ponderosa pine bears S 75°E, 23.5 feet, scribed T1N R34E S33 BT.
- A 23" ponderosa pine bears N 64 1/2°W, 58.9 feet, scribed T1N R34E S29 BT.

No acceptable bearing tree is available in the Southwest quadrant.

Attached "Bearing Object" signs to each of the bearing trees.

Set steel fence post East of corner and attached "Witness Corner" sign.

REGISTERED PROFESSIONAL LAND SURVEYOR <i>William R. Wells</i> OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of the Survey Dept. County of Umatilla
 State of OR, I hereby certify that the within instrument was filed in this office
 for record on the 16th day of January, 1990
David H. Kumbstein by Kathleen J. Ambsberg
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
 Umatilla County Surveyor
 Date 1-90
 Rec'd by KA
 No. 97-02-B