

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 9/28/94

CORNER DESIGNATION: Z-15. South 1/4 corner Section 34, T1N., R34E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. Notes state: "Set basalt stone, 10x9x8 ins., 6 ins. in the ground, for 1/4 sec. cor. marked S C 1/4 on N. face and raised mound of stone 1 1/2 ft. high, 3 1/2 ft. base over it."

MONUMENT AND ACCESSORIES FOUND: None. Corner falls in active hay field. Re-established corner by single proportionate measurement between the recovered Southwest corner of Section 34 and the recovered Southeast corner of Section 35, using James P. Currin and James Noland record under GLO Contract dated May 4, 1887.

MONUMENT MARKING DETAIL:

T1N R34E
1/4 S34

SC
T1S R34E
1994
PLS 1106

MONUMENT SET: At position determined by survey, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe, 30" in the ground, (marked as shown in the monument detail). Top of cap set 3" below surface of hay field.

New Accessories:

Set steel fence post 1.0 foot North of monument.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 27° E-23.7 feet, top set 8" under ground surface.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 18° E-31.7 feet, top set 5" under ground surface.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 23° W-37.4 feet, top set 7" under ground surface.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 52° W-27.7 feet, top set 12" under ground surface.
Attached bearing object sign to each iron pin.

LOCATION & COMMENTS: Corner falls in active hay field.

STATE PLANE CO-ORDINATE:

Oregon North Zone, NAD 83/91, U.S. Survey Foot:
N = 679966.02
E = 8702113.42

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: Robert D. English
Notes: Robert D. English
Witness: F. Scot Munro

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/96

RECEIVED BY

Umatilla County Surveyor

Date 2-95

Rec'd By SK

No. 95-16-C