

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 7/11/94

CORNER DESIGNATION: Z-19. South 1/4 corner Section 35, T1N., R34E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. Notes state: "Set basalt stone, 20x16x6 ins., 14 ins. in the ground for 1/4 sec. cor. marked S C 1/4 on N. face and raised mound of stone 2 ft. high, 4 1/2 ft. base alongside."

MONUMENT AND ACCESSORIES FOUND: None. Corner re-established by single proportionate measurement between the recovered Southwest corner Section 34 and the recovered Southeast corner Section 35, using James P. Currin and James Noland record under GLO Contract dated May 4, 1887.

MONUMENT MARKING DETAIL:

T1N R34E
1/4 S35

SC
T1S R34E
1994
PLS 1106

MONUMENT SET: At position determined by survey, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe, 26" in the ground, with mound of stone to cap, (marked as shown in the monument detail).

New Accessories:

Set steel fence post with witness sign attached, 1.8 feet north of monument.

A 15" white fir bears N 27° W-25.2 feet, scribed: 1/4S35 SC BT.

A 26" white fir bears N 13° W-28.5 feet, scribed: 1/4S35 SC BT.

A 13" white fir bears N 0 1/2° W-16.3 feet, scribed: 1/4S35 SC BT.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106" bears N 85° E-15.3 feet.

Attached bearing object sign to iron pin. Set steel fence post near iron pin with witness sign attached. Bearing trees have a brass washer stamped 'PLS 1106' nailed to the face of the blaze. Attached bearing object and witness signs to each tree; painted a 6" band and face of blaze red.

LOCATION & COMMENTS:

STATE PLANE CO-ORDINATE:

Oregon North Zone, NAD 83/91, U.S. Survey Foot:

N = 680096.86

E = 8707464.69

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: Robert D. English
Notes: Robert D. English
Witness: F. Scot Munro

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/96

RECEIVED BY
Umatilla County Surveyor
Date 2-95
Rec'd By KB
No. 95-16-C