

Witnessed by:

R. Hemmer
L. Boge
L. Hettema

1/4 Corner Sections 20 and 29 R-7

Original:

Set post 3' long, 3" square, 24" in ground, marked "1/4 S" on north face (not found).

36" fir N45°W, 29 links "1/4 S BT" (not found).

12" pine S69°E, 30 links "1/4 S BT" (not found).

Parks Crew Reestablishment:

Set: 5/8" x 30" capped iron rod marked "Oregon State Parks".

7' steel post with white boundary paddle marked "Oregon State Park Boundary Do Not Disturb" 2.0 east of iron rod.

12" fir S42 1/2°W, 14.2' to center, scribed "N 1/4 S29 BT RS691".

9" Tamarack N10°W, 26.0' to center, scribed "S 1/4 S20 BT". Set Parks' corner tag.

Corner is 11.0' west of a north-south fence line and 1.0' north of a 28" fir, and 6.3' south of a 2" yew.

Witnessed by:

R. Hemmer
L. Boge
L. Hettema

East 1/16 Corner Sections 20 and 29 R-8

Parks Crew Set:

5/8" x 30" capped iron rod with aluminum cap marked "Oregon State Parks".

7' steel post with white boundary paddle marked "Oregon State Park Boundary Do Not Disturb", 2.0' west of iron rod.

21" fir S41°W, 14.0' to center, scribed "E1/16 S29 BT".

6" red fir N18°W, 14.9' to center, scribed "E1/16 S20 BT RS691". Set Parks corner tag.

Corner is N64°W, 90' from 1 1/2' wide creek, course north-south.

Witnessed by:

R. Hemmer
L. Boge
L. Hettema

RECEIVED BY

Matilla County Surveyor

Date _____

held by, BLS _____

No. S-124 _____

Section Corner

20	21
29	28

 R-9

Original:

Var. 20°

Set basalt stone 14"x12"x10", 8" in ground for corner Sections 20, 21, 28 and 29. Marked 2 notches on south and 4 notches on east edges. (Parks crew found 12"x5" stone with "X" on top solidly in ground with 4" showing out of ground; notches were not visible.)