

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla      DATE: 8/06/97

CORNER DESIGNATION: V-15, North 1/4 corner Section 34, T1N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by James P. Currin and James Noland, under Special Contract, dated May 4, 1887. Notes state: Set post 3 ft. long 3 ins. square, 24 ins. in the ground for 1/4 S. corner, marked 1/4 S in N. face from which:

A pine 10 ins. in diam. bears N 63° W 30 lks. dist., marked 1/4 S. BT.

A pine 10 ins. in diam. bears S 20° W 40 lks. dist., marked 1/4 S. B.T.

MONUMENT AND ACCESSORIES FOUND: No evidence of corner post or original bearing trees was found. Re-established corner on line between the Northwest corner of Section 34 and the re-established location for the closing corner on the Umatilla Indian Reservation Boundary. Corner point was established on line between above referenced corners at a point 0.50 chains (33 feet) East of the spring branch called for in original notes. Note: There are now two spring branches, the most westerly branch is the original branch. The east branch was formed by damming of the spring branch. From the re-established corner position, a fence corner bears S 89° W 22 ft., with fences extending South and West.

**MONUMENT MARKING DETAIL:**

T1N R35E  
S 27  
1/4 -----  
S 34  
1997  
PLS 1106

**MONUMENT SET:**

At position determined by survey, set a 2 1/2" aluminum cap on 2 1/2" by 30" aluminum pipe, 22" in the ground and surrounded with a mound of earth and stone. Cap marked as shown in corner diagram.

**New Accessories:**

A 4" lodgepole pine bears N 78° E 15.5' scribed "X" at breast height and "BT" at base.

A 11" western larch bears S 02° W 9.1' scribed 1/4 S34 BT.

A 13" western larch bears S 54° W 33.9' scribed 1/4 S34 BT.

A 10" lodgepole pine bears N 59° W 54.5' scribed 1/4 S27 BT.

Attached witness sign to steel fence post 3' East of corner. Attached bearing object signs to the bearing trees.

LOCATION & COMMENTS: Corner located near N-S drainage, about 30' South of a dirt road.

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, Oregon 97801

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

Witness: John Linder & Jason Wells.

*William R. Wells*  
OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-98*

*97-156-B*