

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V - 21
DIAGRAM

History of original corner establishment:

The original corner was established by Manius Buchanan on June 21, 1895, under GLO contract No. 635, as follows:

Set a fir post for the corner to sections 25, 26, 35 and 36, properly marked, from which:

- A 16" black pine bears N70°E, 58 links (38.28 feet).
- A 15" black pine bears S36°E, 26 links (17.16 feet).
- A 6" black pine bears S50° 30'W, 58 links (38.28 feet).
- A 20" black pine bears N71° 45'W, 27 links (17.82 feet).

Corner evidence recovered:

A sawn, decayed and burnt Ponderosa Pine stump, size indeterminate, with scribes for section 26 visible, bears N71° 45'W, 17.8 feet.

A decayed, burnt and fallen Ponderosa Pine, with scribes for section 25 visible, root hole bears N70°E, 38.3 feet.


Monument and accessories established to perpetuate the original position of this corner:

At the point for the corner, as determined by reference to the original bearing tree evidence recovered, I set a 1" x 30" flared, galvanized iron pipe 22" into the ground. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I build a mound of stones around the pipe, from which:

- A 21" Ponderosa Pine, scribed "T1N R35E S25 BT", bears N85° 30'E, 21.6 feet.
- A 18" Ponderosa Pine, scribed "T1N R35E S36 BT", bears S26°E, 19.6 feet.
- A 21" Ponderosa Pine, scribed "T1N R35E S35 BT", bears S2° W, 19.3 feet.
- A 20" Douglas-fir, scribed "T1N R35E S26 BT", bears N24°W, 37.7 feet.

The new bearing trees are scribed on double blazes and have a 3/4" brass washer, marked "PLS 1636", nailed flush to the bottom of the lower blaze. A fence corner, with fences projecting north and west, bears S10°W, 18 feet.

I hereby certify the above corner point was perpetuated as hereon described on October 18, 2001. Magnetic declination set in compass: 18°E.



Dennis L. Gaylord

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 2001.

Umatilla County Surveyor

Date 10-01

Rec'd by RF

nr. A1-158-R