

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 9/6/94

CORNER DESIGNATION: Z-23. South 1/4 corner Section 36, T1N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. Notes state: "Set basalt stone 16 x 12 x 10 ins. 10 ins. in the ground in exact spot of old post cor., which is badly decayed, for 1/4 sec. cor., marked S.C. 1/4 on N. face, from which: A Pine, 36 ins. in diam. bears S.70°E 48 lks. dist., marked S.C.1/4 S.B.T. A Pine, 14 ins. in diam. bears S35°E 112 lks. dist., marked S.C.1/4 S.B.T." References to old corner and accessories are from original corner establishment by Timothy Davenport, Contract No. 102, dated July 20, 1863.

MONUMENT AND ACCESSORIES FOUND:

A 13" x 9" x 6" stone marked 1/4 on North face.
A 28" ponderosa pine stump bears S 70° E-31.7 feet to center of tree, with scribe marks 'BT' visible on open blaze.

MONUMENT MARKING DETAIL:

T1N R35E
S36
1/4 -----

T1S R35E
1994
PLS 1106

MONUMENT SET:

At position of found corner stone, set a 2 1/2" brass cap on 1 1/4" x 30" galvanized iron pipe, 21" in the ground with small mound of stone to cap, placed corner stone South of monument in mound (cap marked as shown in monument detail).

New Accessories:

Set steel fence post 2.2 feet North of monument with witness sign attached.

A 12" ponderosa pine bears N 53° E-44.3 feet, scribed: 1/4 S36 SC BT.

A 14" douglas fir bears N 84° W-40.1 feet, scribed: 1/4 S36 SC BT.

A 5" ponderosa pine bears N 41 1/2° W-119.2 feet, scribed: "X" at breast height and "BT" at base of tree.

An 8" ponderosa pine bears N 34° W-126.7 feet, scribed: 1/4 S36 SC BT.

Bearing trees have a brass washer stamped 'PLS 1106' nailed to the face of the blaze. Attached bearing object and witness signs to each tree, painted a 6" band and face of blaze red.

LOCATION & COMMENTS: Located on very steep hillside.

STATE PLANE CO-ORDINATE:

Oregon North Zone, NAD 83/91, U.S. Survey Foot:

N = 681009.40
E = 8744653.70

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: Robert D. English
Notes: Robert D. English
Witness: F. Scot Munro

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will: R. Wells

OREGON
JULY 22, 1997
WILLIAM R. WELLS
1106

Renews 6/30/96

RECEIVED BY
Umatilla County Surveyors
Date 2-95
Rec'd By KK
2-16-C