

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 7/26/94

CORNER DESIGNATION: Z-3. South 1/4 corner Section 31, T1N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. Notes state: "Exact point of old 1/4 sec. cor and set post 3 ft. long, 3 ins. square, 24 ins. in the ground for 1/4 sec. cor., marked 1/4S.S.C. on N. face, from which: A Pine 12 ins. in diam. bears S15°E.29 lks. dist., marked S.C. 1/4 S.B.T. A Pine 30 ins. in diam. bears N.30°W. 40 lks. dist., marked S.C.1/4S.B.T. These are original bearing trees." Original bearing trees from survey made by Timothy Davenport, under Contract No. 102, dated July 20, 1863." Re-monumented by PLS 1099 in 1983, in survey No. 83-184-R.

MONUMENT AND ACCESSORIES FOUND: Found 2 1/2" brass cap on a 2 1/2" pipe, protruding 3" out of the ground, with stone along side, (marked as shown in the monument detail).

Bearing Trees:

A 19" douglas fir bears N 53° W-28.5 feet, with healed blaze, (LS 1099 bearing tree).
An 11" western larch bears N 27°E-19.4 feet, with visible scribing, (LS 1099 bearing tree).
A 13" stump bears S 16° E-19.4 feet, with visible scribing, (Davenport bearing tree).
A 24" stump bears N 31° W-27.7 feet, with blaze, no visible scribing, (Davenport bearing tree).

MONUMENT MARKING DETAIL:

T1N
1/4
S31 R
-----35
T1S E
PLS 1099
1986

MONUMENT SET:

Set steel fence post 2.4 feet North of monument with witness sign attached.

New Accessories:

A 19" douglas fir bears N 34° W-42.6 feet, scribed: 1/4 S31 BT.
A 15" douglas fir bears N 85° E-47.6 feet, scribed: 1/4 S31 BT.
Bearing trees have a brass washer stamped 'PLS 1106' nailed to the face of the blaze. Attached bearing object and witness signs to each tree, painted a 6" band and face of blaze red.

LOCATION & COMMENTS:

STATE PLANE CO-ORDINATE:

Oregon North Zone, NAD 83/91, U.S. Survey Foot:
N = 680348.76
E = 8718030.04

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: Robert D. English
Notes: Robert D. English
Witness: F. Scot Munro

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/96

RECEIVED BY

Umatilla County Surveyor
Date 2-95
Rec'd By KK
No. 95-16-C