

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:


Corner established in 1998, by Kaiser/Griffin/ Seibold, Cadastral Surveyors under Bureau of Land Management Group No.1844. The BLM records state:

Point for the center 1/4 sec. cor. of sec. 4, at intersection with the E. and W. centerline

Set a stainless steel post, 28 ins. long, 2-1/2 ins. diam., 23 ins. in the ground, with brass cap mkd. from which:

A ponderosa pine, 12 ins. diam., bears S.63-1/2°E., 62 lks. dist., mkd. C 1/4 S4 BT.
A fir, 17 ins. diam., bears S.78-1/4° W., 20 lks. dist., mkd. C 1/4 S4 BT.

Deposited a magnet in a white plastic case at the base of the stainless steel posts.



Description of corner evidence found:

Found 3-1/4" brass cap marked per the diagram on 2-1/2" pipe, 0.6 feet above ground in rock mound.

Burnt and dead 12" Ponderosa Pine bears S.63°30'W., 40.9 feet. (BLM Bearing Tree)
Burnt and dead 17" Fir bears S.78°W., 13.2 feet. (BLM Bearing Tree)

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 5/8" x 24" rebar with 1-1/2" aluminum cap, bears S.84°W., 28.6 feet, stamped WSI/RM 28.6, 2535.
Set 5/8" x 24" rebar with 1-1/2" aluminum cap, bears S.80°E., 27.0 feet, stamped WSI/RM 27.0, 2535.
Set 5/8" x 24" rebar with 1-1/2" aluminum cap, bears N.08°W., 15.7 feet, stamped WSI/RM 15.7, 2535.
Set 5/8" x 24" rebar with 1-1/2" aluminum cap, bears S.24°E., 17.1 feet, stamped WSI/RM 17.1, 2535.

Reference monuments have an arrow pointing towards the corner. Appropriate signs have been attached to all bearing trees as required by this US Forest Service contract. 20° declination was used. Fieldwork was performed in May 2002.

REGISTERED PROFESSIONAL LAND SURVEYOR

Michael P. LeJeune

OREGON JAN. 21, 1992 MICHAEL P. LE JEUNE 2535

Expires 12/31/02

Prepared by: White Shield, Inc. 2515 W. Falls Ave. Kennewick, WA 99336

Michael P. LeJeune, Oregon PLS. 2535

Office ofCounty Surveyor....., County ofUmatilla.....,State of Oregon, I hereby certify that the within instrument was filed in this office for record on theday of 20.....

David H. ...
(County Official)

RECEIVED BY
(Deputy) **Umatilla County Surveyor**

Date 11-02
Rec'd By KK
" 22-172-R