

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:


Corner established in 1998, by Kaiser/Griffin/ Seibold, Cadastral Surveyors under Bureau of Land Management Group No. The BLM records state:

Point for the S 1/16 sec. cor. of sec. 4 and 5.

Set a stainless steel post, 28 ins. long, 2-1/2 ins. diam., 22 ins. in the ground, in collar of stone, with brass cap from which:

No bearing trees available within limits.

Deposited a magnet in a white plastic case at the base of the stainless steel posts.



Description of corner evidence found:

Found 3-1/4" brass cap marked per the diagram on a 2-1/2" pipe.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 5/8" x 24" rebar with 1-1/2" aluminum cap, bears East, 46.6 feet, stamped WSI/RM 46.6, 2535.

Set 5/8" x 24" rebar with 2" aluminum cap, bears South, 42.2 feet, stamped WSI/RM 42.2, 2535.

Reference monuments have an arrow pointing towards the corner. Appropriate signs have been attached to all bearing trees as required by this US Forest Service contract. 20° declination was used. Fieldwork was performed in May 2002.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Michael P. LeJeune

OREGON 11/06/02
JAN. 21, 1992
MICHAEL P. LE JEUNE
2535
EXPIRES 12/31/02

Prepared by: White Shield, Inc.
2515 W. Falls Ave.
Kennewick, WA 99336

Michael P. LeJeune,
Oregon PLS. 2535

Office ofCounty Surveyor....., County ofUmatilla.....,State of Oregon, I hereby certify that the within

instrument was filed in this office for record on theday of
David H. Lee
(County Official) by
(Deputy)

RECEIVED BY
Umatilla County Surveyor
Date 11-02
Rec'd By KK
No. 02-273-B