


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

NONE

N-11.46
349400
T. 1 N., R. 36 E.
Witness Point 2 of sections 16 & 21



Description of corner evidence found:

NONE

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2" diameter by 30" long aluminum pipe, with 3 1/4" diameter aluminum cap, 27" in the ground, marked as shown, from which:

- 8" Ponderosa Pine bears N 67 1/2° E, 34.1 feet, scribed "WP2 S16" "BT".
- 11" Ponderosa Pine bears S 58 1/2° W, 37.1 feet, scribed "WP2 S21" "BT".

The new bearing trees are double blazed and have a 3/4" diameter brass washer stamped "RLS 2308" nailed to the lower blaze between the scribed "B T".



DATUM: NAD83(1991) Oregon High Accuracy Reference Network
 STATE PLANE COORDINATES: Oregon North Zone in International Feet
 No. Latitude Longitude Northing(Y) Easting(X)
 349400 45°33'31.00724" N. 118°18'57.10985" W. 697319.310' 8761469.287'

REGISTERED PROFESSIONAL LAND SURVEYOR

David A. Schlaich

OREGON
JULY 16, 1987
DAVID A. SCHLAICH
2308

RENEWAL DATE: 06/30/2004

Work Performed By: David A. Schlaich (RLS 2308)
 Witnessed By: Matthew Duffy
 Equipment: Topcon GPT-6005C Total Station
 Magnetic Declination: 17 1/2° East
 Date: September 5, 2002

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 20.....
 by.....
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

SEE MAP OF SURVEY NO. D3-31-B