

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 7/28/94

CORNER DESIGNATION: Z-25. Southeast corner Section 36, T1N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Record by James P. Currin and James Noland, under Special Contract dated May 4, 1887 states: "Cor. is a post 4 1/2 ft. long, 4 ins. square set firmly in the ground marked S.C.T.1 N. on N.; S31R36E on E., and S36R35E on W. faces with 6 notches on N.E. and W. edges, from which: A Spruce, 8 ins. in diam. bears N 30 E 31 lks. dist., marked S.C.T.1N.R.36E.S31 B.T. A Pine, 14 ins. in diam. bears N15°W.37 lks. dist., marked S.C.T.1 N.R.35E.S36 B.T. A Pine, 12 ins. in diam. bears S.50°W.32 lks. dist., marked S.C.T.1 S.R.36 E.B.T." Reference to corner and accessories by Currin and Noland refer to original corner record by Timothy Davenport under Contract No. 102, dated July 20, 1863. Corner recovered by BLM in 1983, records state: "The standard cor. to T. 1 N., Rs. 35 and 36 E., determined at record distance from the original bearing trees: A spruce, 24 ins. diam., bears N. 17° E, 31 lks. dist., with scribe marks R36 visible on opened blaze and healed lower blaze. (Record, N. 60° E.) A fir, 14 ins. diam., bears N. 60° W., 37 lks. dist., with scribe marks BT visible on opened lower blaze and healed upper blaze. (Record, pine, N. 15° W.) At the corner point Set an iron post, 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground, with brass cap (marked as shown in monument detail). from which a new bearing tree A fir, 28 ins. diam., bears N. 79° W., 52 lks. dist., mkd. T1N R35 E S36 SC BT."

MONUMENT AND ACCESSORIES FOUND:

A 3 1/4" brass cap (BLM) on 2 1/2" galvanized iron pipe, protruding 6" out of ground, (marked as shown in monument detail).

Bearing Trees:

A 24" uprooted douglas fir bears N 17° E-20.2 feet, (Davenport bearing tree).

A 14" white fir bears N 60° W-24.4 feet, 2 foot stump, 'BT' visible, (Davenport bearing tree).

A 30" douglas fir bears N 79° W-33.8 feet, scribed, pitched over, (BLM bearing tree).

MONUMENT MARKING DETAIL:

U.S. DEPT INT.
SC
T1N
R35E R36E
S36 | S31

1983
B L M

MONUMENT SET:

New Accessories:

Attached witness sign to existing steel fence post 3.3 feet North of monument.

A 29" ponderosa pine bears N 79° E-59.3 feet, scribed: T1N R36E S31 SC BT.

A 12" tamarack bears N 52° W-62.8 feet, scribed: T1N R35E S36 SC BT.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372", bears N 48° E-16.6 feet.

Bearing object sign attached to iron pin. Set a steel fence post near iron pin with witness sign attached. Bearing trees have a brass washer stamped 'PLS 1106' nailed to the face of the blaze. Attached bearing object and witness signs to each tree, painted a 6" band and face of blaze red.

LOCATION & COMMENTS:

RECEIVED BY

Umatilla County Surveyor

Date 2-95

Rec'd By KK

No. 95-16-C

STATE PLANE CO-ORDINATE:

Oregon North Zone, NAD 83/91, U.S. Survey Foot:

N = 681033.54

E = 8747317.12

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: Robert D. English
Notes: Robert D. English
Witness: F. Scot Munro

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/96

RECEIVED BY

Umatilla County Surveyor

Date 2-95

Rec'd By KK

No. 95-16-C