


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Jacob C. Cooper under GLO contract number 397, dated July 1, 1881. Surveyor General record states:

A thorn tree 3 ins diam which I marked for $\frac{1}{4}$ sec cor $\frac{1}{4}$ S on the E and W faces, from which:

A balm 28 ins diam bears S80°W, 15 lks dist marked $\frac{1}{4}$ S BT
No other suitable trees in limits and raised a mound of stone alongside.



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Found no evidence of the original corner monument or accessories.

See map of survey dated September, 1989.

Description of monument and accessories I established to perpetuate the

original location of this corner: At position determined by survey, I set a 2 $\frac{1}{2}$ " x 30" aluminum pipe with aluminum cap marked as shown, 27 inches in the ground, from which:

New Bearing Trees:

A 33 inch diameter White Fir bears N45°E, 82.45 feet marked $\frac{1}{4}$ S30 BT
A 28 inch diameter Ponderosa Pine bears S29°W, 56.62 feet marked $\frac{1}{4}$ S25 BT

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs.

Set a steel fence post approximately 5 feet South with Land Survey Monument sign attached.

Raised a mound of stone around monument, 3 ft. base to top of cap.

I hereby certify that the above corner point was perpetuated as hereon described on September 11, 1989.

Witness: Rick Robinson.



I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of the Survey Dept County of Umatilla
State of OR, I hereby certify that the within instrument was filed in this office for record on the 27 day of October, 1989
David H. Robinson by Kathleen K. Anderson
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date: 10-89

Rec'd By: KA

No: 89-1A1-B

*GPO-591-971, 1988